


Express Oil Change – Stillwater, OK

Geotechnical Engineering Report

October 18, 2024 | Terracon Project No. 04245192

Prepared for:

Express Oil Change, LLC
1800 Southpark Drive
Birmingham, Alabama 35244



Nationwide
[Terracon.com](https://www.terracon.com)

- Facilities
- Environmental
- Geotechnical
- Materials



9522 East 47th Place, Unit D
Tulsa, Oklahoma 74145
P (918) 250-0461
Terracon.com

October 18, 2024

Express Oil Change, LLC
1800 Southpark Drive
Birmingham, Alabama 35244

Attn: Mr. Tyler Hendon
P: (205) 337-2967
E: tyler.hendon@expressoil.com

Re: Geotechnical Engineering Report
Express Oil Change – Stillwater, OK
4420 West 6th Avenue
Stillwater, Oklahoma
Terracon Project No. 04245192

Dear Mr. Hendon:

We have completed the scope of Geotechnical Engineering services for the above referenced project in general accordance with Terracon Proposal No. P04245192 dated September 24, 2024. This report presents the findings of the subsurface exploration and provides geotechnical recommendations for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,

Terracon

Cert. Of Auth. #CA-4531 exp. 6/30/25

Ali Vafaei, E.I.
Senior Staff Engineer

APR reviewed by: Michael H. Homan, P.E.
Senior Principal

Nate Braithwaite, P.E.
Oklahoma No. 29249

10/18/2024





Table of Contents

Introduction..... 1

Project Description..... 1

Site Conditions 2

Geotechnical Characterization 3

Seismic Site Class..... 4

Geotechnical Overview 5

Earthwork 5

 Site Preparation..... 6

 Subgrade Preparation 6

 Existing Fill 6

 Fill Material Types 7

 Fill Placement and Compaction Requirements 8

 Utility Trench Backfill 8

 Grading and Drainage..... 8

 Earthwork Construction Considerations 9

 Construction Observation and Testing 10

Shallow Foundations 11

 Footing Foundation Design Recommendations 11

 Footing Foundation Construction Considerations 11

Floor Slabs 13

 Floor Slab Design Recommendations 13

 Floor Slab Construction Considerations 14

Lateral Earth Pressures 14

 Design Parameters..... 14

 Subsurface Drainage for Below-Grade Walls 16

Below-Grade Structures..... 17

Pavements 17

 General Pavement Comments 17

 Pavement Section Thicknesses 18

 Pavement Drainage 19

 Pavement Maintenance 19

General Comments 20

Figures

GeoModel


Attachments

Exploration and Testing Procedures

Site Location and Exploration Plans

Exploration and Laboratory Results

Supporting Information

Note: This report was originally delivered in a web-based format. **Blue Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the  logo will bring you back to this page. For more interactive features, please view your project online at client.terracon.com.

Refer to each individual Attachment for a listing of contents.

Introduction

This report presents the results of our subsurface exploration and Geotechnical Engineering services performed for the Express Oil Change to be located at 4420 West 6th Avenue in Stillwater, Oklahoma. The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil
- Groundwater conditions
- Seismic site classification per IBC
- Site preparation and earthwork
- Foundation design and construction
- Floor slab design and construction
- Lateral earth pressure
- Pavement design and construction

The geotechnical engineering Scope of Services for this project included the advancement of test borings, laboratory testing, engineering analysis, and preparation of this report.

Drawings showing the site and boring locations are shown on the [Site Location](#) and [Exploration Plan](#), respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs and/or as separate graphs in the [Exploration Results](#) section.

Project Description

Our initial understanding of the project was provided in our proposal and was discussed during project planning. Our final understanding of the project conditions is as follows:

Item	Description
Information Provided	An email request for proposal was provided by Tyler Hendon on September 13 th , 2024. The request included a Parcel Map and conceptual plan drawing of the layout of the planned development and proposed boring locations and depths.
Proposed Structure	The structure associated with the project is an approximately 5,900 square foot single-story building with a below-grade oil change pit, paved parking area.

Item	Description
Finished Floor Elevation	Not provided.
Maximum Loads (assumed)	<p>Anticipated structural loads:</p> <ul style="list-style-type: none"> Columns: 25 kips Walls: 2.5 kips per lineal foot (klf) Floor Slabs: 150 pounds per square feet (psf), uniform <p>If this information is not correct, we should be notified to assess the impact of the new information on our recommendations.</p>
Grading/Slopes	A grading plan was not provided at the time of this report. Thus, we have assumed maximum cut and fill depths of 2 feet, relative to the existing grades, will be required to develop the final subgrade elevations for the building and pavements.
Below-Grade Structures	Oil change "Pit" area under the center bay of the building. Pit typically extends 10 feet below finish floor slab.
Free-Standing Retaining Walls	No free-standing retaining walls are planned.
Pavements	<p>Both rigid and flexible pavement sections are considered for this site. Anticipated traffic is as follows:</p> <p>Light Duty:</p> <ul style="list-style-type: none"> Autos/light trucks: 500 vehicles per day <p>Heavy Duty: (in addition to autos/light trucks)</p> <ul style="list-style-type: none"> Trucks: 5,000 vehicle per year
Building Code	2018 IBC

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration.

Item	Description
Parcel Information	<p>The project is located at 4420 West 6th Avenue in Stillwater, Oklahoma.</p> <p>Latitude/Longitude (approximate) 36.1168° N/97.1183° W</p> <p>See Site Location</p>

Item	Description
Existing Improvements	None
Current Ground Cover	Grass and trees
Existing Topography	Relatively level; about 1 foot of maximum elevation difference between the borings throughout the site.

Geotechnical Characterization

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting, and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in the [Exploration Results](#) and the GeoModel can be found in the [Figures](#) attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Model Layer	Layer Name	General Description
1	Fill	Clayey Sand with varying amounts of gravel and sandstone fragments
2	Native Soils	Sandy Silty Lean Clay (CL-ML); Sandy Lean Clay (CL) with silt lenses; Sandy Lean Clay (CL) trace gravel; Silty Sand (SM)

The boreholes were observed while drilling and immediately after completion for the presence and level of groundwater. The water levels observed in the boreholes can be found on the boring logs in [Exploration Results](#) and are summarized below.

Boring	Approximate Depth to Groundwater while Drilling ¹ (feet)	Approximate Depth to Groundwater after Drilling ¹ (feet)	Approximate Depth to Groundwater after 48 hours ¹ (feet)
B-1	12.5	Not encountered	11.5
B-2	12	12	Not measured

1. Below ground surface

Groundwater was not observed in the remaining borings while drilling, or for the short duration the borings could remain open. However, this does not necessarily mean the borings terminated above groundwater, or the water levels summarized above are stable groundwater levels. Due to the low permeability of the soils encountered in the borings, a relatively long period may be necessary for a groundwater level to develop and stabilize in a borehole. Long term observations in piezometers or observation wells sealed from the influence of surface water are often required to define groundwater levels in materials of this type.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff, and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project.

Seismic Site Class

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC).

Based on the soil properties observed at the site and as described on the exploration logs and results, and the anticipated fill depths to grade the site, our professional opinion is for that a **Seismic Site Classification of D** be considered for the project. Subsurface explorations at this site were extended to a maximum depth of 20 feet. The site properties below the maximum boring depth were estimated based on our experience and knowledge of geologic conditions of the general area. Upon request, we

could perform deeper borings or geophysical testing to confirm the conditions below the current maximum boring depth.

Geotechnical Overview

Based on the results of the borings and anticipated grade changes, the building can be supported on footings bearing in tested and approved, existing fill or new engineered fill. The **Footing Foundations** section addresses the design and construction of footing foundations for the building.

The soils within the anticipated depth of seasonal moisture change appear suitable for supporting the building floor slabs provided the recommended proof-rolling and moisture/density control outlined in **Earthwork** are incorporated into subgrade preparation and fill placement. The **Floor Slabs** section addresses slab-on-grade support of the building addition.

Constructing the planned building over existing fill is discussed in this report. Because of the potential for variation in the composition and quality of existing fill and unsuitable materials to be buried in existing fills, there is an inherent risk of unpredictable settlement of footings and floor slabs constructed over undocumented existing fills. This risk cannot be eliminated unless the full depth of the existing fill is removed and replaced with tested and approved, new engineered fill.

Our opinion of pavement section thickness design has been developed based on our understanding of the intended use, assumed traffic, and subgrade preparation recommended herein. The **Pavements** section includes minimum pavement component thickness.

The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the **Exploration Results**), engineering analyses, and our current understanding of the proposed project. The **General Comments** section provides an understanding of the report limitations.

Earthwork

Earthwork is anticipated to include subgrade preparation and engineered fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs and pavements.

Site Preparation

Site preparation for the proposed project should include stripping and clearing to remove any trees, surface vegetation, topsoil, debris, and any other unsuitable surface materials from the areas of planned construction. Tree stumps and major root systems should be removed full depth. The depressions or excavations created during removal of trees should be cleaned of loose material and water and backfilled as outlined in the following paragraphs. Actual removal depths should be determined at the time of construction by a representative of the geotechnical engineer.

Subgrade Preparation

The soils encountered within the anticipated depth of seasonal moisture change were low plasticity clays. These soils are not expected to exhibit significant volume changes with variations in the subgrade moisture content. Therefore, the near surface soils are expected to provide adequate support for the on-grade floor slab, provided the procedures outlined below for developing a moisture conditioned, compacted and approved pad are followed.

After site stripping and completing any required cuts and overexcavations, but before placing any fill, we recommend the building and pavement areas be proofrolled with a loaded, tandem-axle dump truck weighing at least 25 tons to locate any zones that are soft or unstable. The proofrolling should involve overlapping passes in mutually perpendicular directions. Where rutting or pumping is observed during proofrolling, the unstable soils should be overexcavated and replaced with an approved material as described herein if it cannot be adequately compacted in-place.

After proofrolling and correcting any unstable subgrade, the exposed subgrade soils should be scarified to a depth of 9 inches. The scarified soil should be moisture conditioned and compacted as recommended in the **Placement and Compaction Requirements** section.

Existing Fill

As noted in **Geotechnical Characterization**, all borings encountered previously placed fill to depths ranging from about 2 to 3.5 feet. We have no records to indicate the degree of control used to place the fill. Existing fill could be present at other locations and extend to varying depths away from the borings. Support of floor slabs and pavements on or above existing fill soils is discussed in this report. However, even with the recommended construction procedures, inherent risk exists for the owner that compressible fill or unsuitable material, within or buried by the fill will, not be discovered. This risk of unforeseen conditions cannot be eliminated without completely

removing the existing fill but can be reduced by following the recommendations contained in this report.

If the owner elects to construct the floor slabs on the existing fill to reduce initial construction costs in exchange for increased potential longer-term distress, the following protocol should be followed. After the planned grading has been completed, the area should be proofrolled. Areas of soft or otherwise unsuitable material should be undercut and replaced with either new structural fill or suitable, existing on site materials.

Fill Material Types

Fill materials should meet the following material property requirements.

Fill Type ¹	USCS Classification	Acceptable Location for Placement
Imported Low Volume Change (LVC) material ² ($8 \leq PI \leq 18$; $\geq 15\%$ material passing No. 200 sieve)	CL; SC	All locations and elevations except where free-drainage material is required
On-Site soil ^{3,4} ($8 \leq PI \leq 18$; $\geq 15\%$ material passing No. 200 sieve)	CL	All locations and elevations except where free-drainage material is required
ODOT Type A Aggregate Base ⁵	GW-GC, GW-GM	Aggregate base course of recommended pavement sections

1. Controlled, compacted fill should consist of approved materials that are free of organic matter and debris and contain maximum rock size of 3 inches. Frozen material should not be used, and fill should not be placed on a frozen subgrade. A sample of each material type should be submitted to the geotechnical engineer for evaluation prior to its use.
2. Approved, imported, low plasticity cohesive soil having a plasticity index (PI) of 8 to 18 and containing at least 15% fines (material passing the No. 200 sieve, based on dry weight). An approved, ODOT Type A aggregate base can be used as LVC fill material.
3. It should be expected that the on-site soils will have elevated moisture levels and require aeration and drying to reduce the soil moisture content to within the recommended range for engineered fills.
4. Undocumented existing fills may contain unsuitable materials and debris that render the existing fill materials unsuitable for reuse as engineered fill. The presence of unsuitable materials and debris may not be identified until construction is underway.
5. Subsection 703.01 of the ODOT Standard Specifications for Highway Construction.

Fill Placement and Compaction Requirements

The scarified and compacted subgrade and engineered fill should meet the following compaction requirements.

Item	Engineered Fill
Subgrade Scarification Depth	9 inches
Maximum Lift Thickness¹	9 inches or less in loose thickness
Minimum Compaction Requirements²	At least 95% of the material's maximum standard Proctor dry density (ASTM D698)
Moisture Content³	Imported LVC Material and On-Site Soils: -2% to +2% of the material's optimum moisture content (ASTM D698) Aggregate Base: Workable moisture Content ³

1. Thinner lifts are recommended in confined areas or when hand-operated compaction equipment is used.
2. We recommend that engineered fill (including scarified compacted subgrade) be tested for moisture content and compaction during placement. Should the results of the in-place density tests indicate the specified moisture or compaction limits have not been met, the area represented by the test should be reworked and retested as required until the specified moisture and compaction requirements are achieved.
3. Workable moisture content is the moisture content sufficient to achieve the specified compaction without causing pumping when proofrolled.

Utility Trench Backfill

Utility trenches are a common source of water infiltration and migration. Utility trenches penetrating beneath the building should be effectively sealed to restrict water intrusion and flow through the trenches, which could migrate below the building. The trench should provide an effective trench plug that extends at least 5 feet from the face of the building exterior. The plug material should consist of cementitious flowable fill or low permeability clay. The trench plug material should be placed to surround the utility line. If used, the clay trench plug material should be placed and compacted to comply with the water content and compaction recommendations for engineered fill stated previously in this report.

Grading and Drainage

All grades must provide effective drainage away from the building during and after construction and should be maintained throughout the life of the structure. Accumulation

of water adjacent to the structure could contribute to significant moisture increases in the subgrade soils and subsequent softening/settlement or expansion/heave, which could result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential floor slab and/or foundation movements, cracked slabs and walls, and roof leaks.

Exposed ground should be sloped and maintained at a minimum 5% away from the building addition for at least 10 feet beyond the perimeter of the building. Locally, flatter grades may be necessary to transition ADA access requirements for flatwork. After building construction and landscaping have been completed, final grades should be verified to document effective drainage has been achieved. Grades around the structure should also be periodically inspected and adjusted, as necessary, as part of the structure's maintenance program. Where paving or flatwork abuts the structure, a maintenance program should be established to effectively seal and maintain joints and prevent surface water infiltration.

Planters located within 10 feet of the building should be self-contained to prevent water accessing the building subgrade soils. Sprinkler mains and spray heads should be located a minimum of 5 feet away from the building lines. Low-volume, drip style landscaped irrigation should not be used near the building. Roof runoff should be collected in drains or gutters. Roof drains and downspouts should be discharged onto pavements which slope away from the buildings or down spouts should be extended a minimum of 10 feet away from structure.

Earthwork Construction Considerations

The on-site lean clay, silty soils, and sandy soils are subject to instability and disturbance with increases in moisture content. If wet conditions occur at the time of construction, equipment mobility will be hindered and it will be necessary to undercut and replace or stabilize the near surface soils to develop suitable support for new fills, floor slabs, shallow foundations, and pavements; and to allow for construction to proceed.

It is not possible to accurately predict until construction is underway the actual quantity of unsuitable soils that will need to be removed. We encourage the owner to secure a base bid for removing a specified quantity of the unsuitable soils. The owner should also secure unit rates for adding or deducting quantities from the base bid that includes costs for exporting unsuitable materials and importing approved replacement materials, if required.

Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of grade-supported improvements such as floor slabs and pavements. Construction traffic over the completed subgrades should be avoided. The site should also be graded to prevent ponding of surface water on the prepared

subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade freezes, desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompact prior to floor slab construction.

We encountered groundwater in the two building borings at depths of about 12 feet. The contractor should be prepared to address groundwater issues when constructing the service pit. We recommend that the groundwater level be kept at least two feet below bottom of excavation for the pit.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local and/or state regulations.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety or the contractor's activities; such responsibility shall neither be implied nor inferred.

Excavations or other activities resulting in ground disturbance have the potential to affect adjoining properties and structures. Our scope of services does not include review of available final grading information or consider potential temporary grading performed by the contractor for potential effects such as ground movement beyond the project limits. A preconstruction/ precondition survey should be conducted to document nearby property/infrastructure prior to any site development activity. Excavation or ground disturbance activities adjacent or near property lines should be monitored or instrumented for potential ground movements that could negatively affect adjoining property and/or structures.

Construction Observation and Testing

The earthwork efforts should be observed by the Geotechnical Engineer (or others under their direction). Observation should include documentation of adequate removal of surficial materials (vegetation, topsoil, and pavements), evaluation and remediation of existing fill materials, as well as proofrolling and mitigation of unsuitable areas delineated by the proofroll.

Each lift of compacted fill should be tested, evaluated, and reworked, as necessary, as recommended by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 2,500 square feet of compacted fill in the building areas and 5,000 square feet in pavement areas, with at least two tests per lift. Where not specified by local ordinance, each lift of backfill should be tested for density and water content at a

frequency of at least one test for every 50 linear feet of compacted utility trench backfill, with at least two tests per lift.

In areas of foundation excavations, the bearing subgrade should be evaluated by the Geotechnical Engineer. If unanticipated conditions are observed, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

Shallow Foundations

The building can be supported on footings bearing in tested and approved, existing fill or new engineered fill. Design and construction recommendations for footing foundations are presented in the following paragraphs.

Footing Foundation Design Recommendations

Item	Description
Maximum Net Allowable Bearing Pressure ¹	2,000 psf
Required Bearing Material	<ul style="list-style-type: none"> ■ Tested and approved, existing fill ■ New engineered fill
Minimum Foundation Dimensions	Columns: 30 inches Continuous: 16 inches
Minimum Depth (below Lowest Finished Grade) ²	24 inches
Estimated Total Settlement	About 1 inch
Estimated Differential Settlement	About ¾ inch or less

1. The net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation.
2. To provide frost protection. Minimum depth applies to perimeter footings and footings in unheated areas.


Footing Foundation Construction Considerations

Footing excavations should be free of loose or disturbed material and water when concrete is placed. Concrete should be placed as soon as possible after excavation is


completed to reduce the potential for wetting, drying, or disturbance of the bearing materials.

To verify that suitable bearing materials are encountered, we recommend the base of all footing excavations be observed and evaluated by the Geotechnical Engineer prior to placing reinforcing steel and concrete. Footing bearing material evaluations should include random hand auger probes at the bottom of footing excavations.

If unsuitable bearing soils are observed at the base of the planned footing excavation, the excavation should be extended deeper to suitable soils, and the footings could bear directly on these soils at the lower level or on lean concrete backfill placed in the excavations. The lean concrete replacement zone is illustrated in the sketch below.



Alternatively, for footings designed to bear in engineered fill, the unsuitable soils can be overexcavated and replaced with tested and approved, engineered fill. Overexcavation for engineered fill placement below footings should be conducted as shown below. The overexcavation should be backfilled up to the footing base elevation with approved engineered fill constructed, as recommended in the **Earthwork** section.



Floor Slabs

Design parameters for floor slabs assume the requirements for **Earthwork** have been followed. Specific attention should be given to positive drainage away from the structure and positive drainage of the aggregate base beneath the floor slab.

The soils within the anticipated depth of seasonal moisture change appear suitable for supporting the building floor slabs provided the recommended proof-rolling and moisture/density control outlined in **Earthwork** are incorporated into subgrade preparation and fill placement.

Floor Slab Design Recommendations

Item	Description
Floor Slab Support¹	On-site materials prepared in accordance with Earthwork
Estimated Modulus of Subgrade Reaction²	100 pounds per square inch per inch (psi/in) for point loads

1. Floor slabs should be structurally independent of building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation.
2. Modulus of subgrade reaction is an estimated value based upon our experience with the subgrade condition, the requirements noted in **Earthwork**, and the floor slab support as noted in this table. It is provided for point loads. For large area loads the modulus of subgrade reaction would be lower.

The use of a vapor retarder should be considered beneath concrete slabs on grade covered with wood, tile, carpet, or other moisture sensitive or impervious coverings, when the project includes humidity-controlled areas, or when the slab will support equipment sensitive to moisture. When conditions warrant the use of a vapor retarder, the slab designer should refer to ACI 302 and/or ACI 360 for procedures and cautions regarding the use and placement of a vapor retarder.

Saw-cut contraction joints should be placed in the slab to help control the location and extent of cracking. For additional recommendations, refer to the ACI Design Manual. Joints or cracks should be sealed with a waterproof, non-extruding compressible compound specifically recommended for heavy duty concrete pavement and wet environments.

Where floor slabs are tied to perimeter walls or turn-down slabs to meet structural or other construction objectives, our experience indicates differential movement between the walls and slabs will likely be observed in adjacent slab expansion joints or floor slab

cracks beyond the length of the structural dowels. The Structural Engineer should account for potential differential settlement through use of sufficient control joints, appropriate reinforcing, or other means.

Floor Slab Construction Considerations


Finished subgrade, within and for at least 10 feet beyond the floor slab, should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until floor slabs are constructed. If the subgrade should become damaged or desiccated prior to construction of floor slabs, the affected material should be removed, and structural fill should be added to replace the resulting excavation. Final conditioning of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should observe the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel, and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

Lateral Earth Pressures

Design Parameters

Structures with unbalanced backfill levels on opposite sides should be designed for earth pressures at least equal to values indicated in the following table. Earth pressures will be influenced by structural design of the walls, conditions of wall restraint, methods of construction, and/or compaction and the strength of the materials being restrained. Two wall restraint conditions are shown in the diagram below. Active earth pressure is commonly used for design of free-standing cantilever retaining walls and assumes wall movement. The “at-rest” condition assumes no wall movement and is commonly used for basement walls, loading dock walls, or other walls restrained at the top. The recommended design lateral earth pressures do not include a factor of safety and do not provide for possible hydrostatic pressure on the walls (unless stated).



Lateral Earth Pressure Design Parameters

Earth Pressure Condition ¹	Coefficient for Backfill Type ²	Surcharge Pressure ³ p_1 (psf)	Equivalent Fluid Pressures (psf) ^{2,4}	
			Unsaturated ⁵	Submerged ⁵
Active (K_a)	Granular - 0.33	$(0.33)S$	$(42)H$	$(83)H$
	Fine Grained - 0.41	$(0.41)S$	$(48)H$	$(85)H$
At-Rest (K_o)	Granular - 0.47	$(0.50)S$	$(63)H$	$(94)H$
	Fine Grained - 0.58	$(0.58)S$	$(68)H$	$(95)H$

1. For active earth pressure, wall must rotate about base, with top lateral movements 0.002 H to 0.004 H , where H is wall height. For passive earth pressure, wall must move horizontally to mobilize resistance. Fat clay or other expansive soils should not be used as backfill behind the wall.
2. Uniform, horizontal backfill, compacted to at least 98% of the ASTM D 698 maximum dry density, with a maximum unit weight of 120 pcf.
3. Uniform surcharge, where S is surcharge pressure.
4. Loading from heavy compaction equipment is not included.
5. To achieve "Unsaturated" conditions, follow guidelines in **Subsurface Drainage for Below-Grade Walls** below. "Submerged" conditions are recommended when drainage behind walls is not incorporated into the design.


Backfill placed against structures should consist of granular soils or low plasticity cohesive soils. For the granular values to be valid, the granular backfill must extend out and up from the base of the wall at an angle of at least 45 degrees from vertical for the active case.

Footings, floor slabs or other loads bearing on backfill behind walls may have a significant influence on the lateral earth pressure. Placing footings within wall backfill and in the zone of active soil influence on the wall should be avoided unless structural analyses indicate the wall can safely withstand the increased pressure.

The lateral earth pressure recommendations given in this section are applicable to the design of rigid retaining walls subject to slight rotation, such as cantilever, or gravity type concrete walls. These recommendations are not applicable to the design of modular block - geogrid reinforced backfill walls (also termed MSE walls). Recommendations covering these types of wall systems are beyond the scope of services for this assignment. However, we would be pleased to develop a proposal for evaluation and design of such wall systems upon request.

Subsurface Drainage for Below-Grade Walls

A perforated rigid plastic drain line installed behind the base of walls and extends below adjacent grade is recommended to prevent hydrostatic loading on the walls. The invert of a drain line around a below-grade building area or exterior retaining wall should be placed near foundation bearing level. The drain line should be sloped to provide positive gravity drainage to daylight or to a sump pit and pump. The drain line should be surrounded by clean, free-draining granular material having less than 5% passing the No. 200 sieve, such as No. 57 aggregate. The free-draining aggregate should be encapsulated in a filter fabric. The granular fill should extend to within 2 feet of final grade, where it should be capped with compacted cohesive fill to reduce infiltration of surface water into the drain system. Compacted on-site clayey sand (SC) or sandy lean clay (CL) should be suitable for the cohesive fill layer shown in the figure below.



As an alternative to free-draining granular fill, a prefabricated drainage structure may be used. A prefabricated drainage structure is a plastic drainage core or mesh which is covered with filter fabric to prevent soil intrusion and is fastened to the wall prior to placing backfill. Prefabricated drainage structures are typically proprietary products that require installation in accordance with manufacturer's installation instructions.

Below-Grade Structures

The project may require an excavation 10 to 12 feet below natural grade. The primary geotechnical considerations affecting the design and construction of the service pit is excavation stability and providing reliable drainage of the underdrain system to prevent hydrostatic uplift conditions. Uplift of the service pit from hydrostatic forces is perhaps the governing factor in design of the proposed structure, and not bearing capacity or settlement. The soils at the site are considered low permeability, so the rate of groundwater infiltration into and out of the service pit excavation should be low. The post construction settlement of the service pit should be minimal.

Typically, subsurface features like the service pit, should be designed to provide at least a factor of safety of 1.2 for uplift with groundwater considered to be at the top of ground, unless a reliable means to maintain the groundwater below the service pit is provided. It is understood that a gravel underdrain system will be provided below the service pit to collect water that infiltrates into the service pit area to prevent a hydrostatic uplift condition. The bottom of the service pit excavation should be sloped to drain water to a collection gallery and a duplex pump system in a sump designed to remove the water to the storm drain system. The underdrain gravel should consist of crushed clean No. 57 gravel that is contained within a non-woven geotextile fabric (Mirafi 140 N or equivalent).

The soil placed above the drainage layer should consist of a compacted, imported lean clay to provide an effective low permeability blanket to minimize surface water infiltration. The soil should be compacted as recommended for General Fill in the **Earthwork** section of this report. The surface grades above the service pit should be appropriately sloped to drain water from the area.

Pavements

General Pavement Comments

Pavement designs are provided for the traffic conditions and pavement life conditions as noted in **Project Description** and in the following sections of this report. A critical aspect of pavement performance is site preparation. Pavement designs noted in this section must be applied to the site which has been prepared as recommended in the **Earthwork** section.

We anticipate the subgrade soils in the pavement areas could consist of tested and approved existing fill, or new engineered fill. Due to engineering properties and variable support characteristics of the anticipated on-site subgrade materials, subgrade improvement should be performed beneath pavements at this site.

Pavement Section Thicknesses

The following table provides our opinion of minimum thickness for Asphaltic Concrete (ACC) and Portland Cement Concrete (PCC) sections:

Minimum Pavement Recommendations¹

Pavement Type	Light Duty	Heavy Duty
Full Depth ACC	2.0" Type "C" Asphaltic Concrete ² 3.0" Type "A" Asphaltic Concrete ² 10.0" LVC Fill OR 2.0" Type "C" Asphaltic Concrete ² 3.0" Type "A" Asphaltic Concrete ² 6.0" Type "A" Aggregate Base ³	2.0" Type "C" Asphaltic Concrete ² 5.0" Type "A" Asphaltic Concrete ² 10.0" LVC Fill OR 2.0" Type "C" Asphaltic Concrete ² 5.0" Type "A" Asphaltic Concrete ² 6.0" Type "A" Aggregate Base ³
	5.0" Concrete 10.0" LVC Fill OR 5.0" Concrete 6.0" Type "A" Aggregate Base ³	6.0" Concrete 10.0" LVC Fill OR 6.0" Concrete 6.0" Type "A" Aggregate Base ³

1. All materials should meet the current Oklahoma Department of Transportation (ODOT) Standard Specifications for Highway and Bridge Construction. For asphaltic concrete, refer to ODOT 1988 Specifications.
2. Type "C" asphaltic concrete is equivalent to Type "S5" PG 64-22 OK and Type "A" asphaltic concrete is equivalent to Type "S3" PG 64-22 OK
3. ODOT Type "A" aggregate base should meet the requirements of Section 703.01. The aggregate should be spread and densified to at least 98 percent of the material's maximum dry density as determined by the standard Proctor test method ASTM D698.

Note: We recommend that reinforced concrete pads be provided in front of and beneath trash receptacles. The dumpster trucks should be parked on the rigid concrete pavement when the trash receptacles are lifted. The concrete pads should be a minimum of 7 inches thick and properly reinforced

PCC pavements will perform better than ACC in areas where short radius turning and braking are expected (i.e., entrance/exit aprons) due to better resistance to rutting and

shoving. In addition, PCC pavement will perform better in areas subject to heavy static loads.

Construction traffic on the pavements was not considered in developing our opinions of minimum pavement thickness. If the pavements will be subject to construction equipment/vehicles, the pavement sections should be revised to consider the additional loading.

Pavements and subgrades will be subject to freeze-thaw cycles and seasonal fluctuations in moisture content. Pavement thickness design methods are intended to provide adequate thickness of structural materials over a particular subgrade such that wheel loads are reduced to a level that the subgrade can support. The subgrade support parameters for pavement thickness design do not account for shrink/swell movements of a subgrade constructed of expansive clay soils. Therefore, the pavement may be adequate from a structural standpoint, yet still experience cracking and deformation due to shrink/swell related movement of the subgrade.

The pavement sections provided above consider that the subgrade soils will not experience significant increases in moisture content. Paved areas should be sloped to provide rapid drainage of surface water and to drain water away from the pavement edges. Pavements should be designed so water does not accumulate on or adjacent to the pavement, since this could saturate and soften the subgrade soils and subsequently accelerate pavement deterioration.

Pavement Drainage

Pavements should be sloped to provide rapid drainage of surface water. Water allowed to pond on or adjacent to the pavements could saturate the subgrade and contribute to premature pavement deterioration. In addition, the pavement subgrade should be graded to provide positive drainage within the granular base section. Appropriate sub-drainage or connection to a suitable daylight outlet should be provided to remove water from the granular subbase.

Pavement Maintenance

The pavement sections represent minimum recommended thicknesses and, as such, periodic upkeep should be anticipated. Preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Pavement care consists of both localized (e.g., crack and joint sealing and patching) and global maintenance (e.g., surface sealing). Additional engineering consultation is recommended to determine the type and extent of a cost-

effective program. Even with periodic maintenance, some movements and related cracking may still occur, and repairs may be required.

Pavement performance is affected by its surroundings. In addition to providing preventive maintenance, the civil engineer should consider the following recommendations in the design and layout of pavements:

- Final grade adjacent to paved areas should slope down from the edges at a minimum 2%.
- Subgrade and pavement surfaces should have a minimum 2% slope to promote proper surface drainage.
- Install pavement drainage systems surrounding areas anticipated for frequent wetting.
- Install joint sealant and seal cracks immediately.
- Seal all landscaped areas in or adjacent to pavements to reduce moisture migration to subgrade soils.
- Place compacted, low permeability backfill against the exterior side of curb and gutter.
- Place curb, gutter and/or sidewalk directly on clay subgrade soils rather than on unbound granular base course materials.

General Comments

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials, or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in

accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly affect excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety and cost estimating including excavation support and dewatering requirements/design are the responsibility of others.

Construction and site development have the potential to affect adjacent properties. Such impacts can include damages due to vibration, modification of groundwater/surface water flow during construction, foundation movement due to undermining or subsidence from excavation, as well as noise or air quality concerns. Evaluation of these items on nearby properties are commonly associated with contractor means and methods and are not addressed in this report. The owner and contractor should consider a preconstruction/precondition survey of surrounding development. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

Geotechnical Engineering Report

Express Oil Change – Stillwater, OK | Stillwater, Oklahoma

October 18, 2024 | Terracon Project No. 04245192




Figures




Contents:



GeoModel (2 pages)

GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.


Model Layer	Layer Name	General Description	Legend	
1	Fill	Clayey Sand with varying amounts of gravel and sandstone fragments		Fill
2	Native Soils	Sandy Silty Lean Clay (CL-ML); Sandy Lean Clay (CL) with silt lenses; Sandy Lean Clay (CL) trace gravel; Silty Sand (SM)		Sandy Silty Clay
				Sandy Lean Clay

-  First Water Observation
 Second Water Observation

Groundwater levels are temporal. The levels shown are representative of the date and time of our exploration. Significant changes are possible over time.
Water levels shown are as measured during and/or after drilling. In some cases, boring advancement methods mask the presence/absence of groundwater. See individual logs for details.

NOTES:
Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description	Legend	
1	Fill	Clayey Sand with varying amounts of gravel and sandstone fragments	Fill	Sandy Silty Clay
2	Native Soils	Sandy Silty Lean Clay (CL-ML); Sandy Lean Clay (CL) with silt lenses; Sandy Lean Clay (CL) trace gravel; Silty Sand (SM)	Silty Sand	Sandy Lean Clay

- First Water Observation
- Second Water Observation

Groundwater levels are temporal. The levels shown are representative of the date and time of our exploration. Significant changes are possible over time.
Water levels shown are as measured during and/or after drilling. In some cases, boring advancement methods mask the presence/absence of groundwater. See individual logs for details.

NOTES:
Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Geotechnical Engineering Report

Express Oil Change – Stillwater, OK | Stillwater, Oklahoma

October 18, 2024 | Terracon Project No. 04245192



Attachments

Exploration and Testing Procedures

Field Exploration

Number of Borings	Approximate Boring Depth (feet)	Location ¹
2 (B-1 and B-2)	15 to 20	Proposed building area
3 (P-1 to P-3)	10	Proposed paved/driveway area

1. The boring locations are shown on the attached **Exploration Plan**.

Boring Layout and Elevations: Terracon personnel staked the boring locations in the field using a handheld GPS unit (estimated horizontal accuracy of about ±25 feet). Terracon determined relative elevations of the borings. Elevations are also approximate and were obtained using an engineer’s level from a convenient reference point. For this exploration, the boring surface elevations were referenced to the top of a manhole cover at the south side of site plan, which was assumed to have an arbitrary elevation of 100.0 feet. The approximate ground surface elevations at the borings, rounded to the nearest 0.5 feet, are shown near the top of the boring logs. The locations and elevations of the borings should be considered accurate only to the degree implied by these methods.

Subsurface Exploration Procedures: We advanced the borings with an ATV-mounted rotary drill rig using continuous flight augers. Five samples were obtained in the upper 10 feet of each boring and at intervals of 5 feet thereafter. In the split barrel sampling procedure, a standard 2-inch outer diameter split barrel sampling spoon was driven into the ground by a 140-pound automatic hammer falling 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. The SPT resistance values, also referred to as N-values, are indicated on the boring logs at the test depths. We observed and recorded groundwater levels during drilling and sampling. For safety purposes, all borings were backfilled with auger cuttings after their completion.

We also observed the boreholes while drilling and at the completion of drilling for the presence of groundwater. A temporary piezometer was installed in boring B-1, and water levels were recorded over a 48 hour period.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our exploration team prepared field boring logs as part of the drilling operations. These field

logs included visual classifications of the materials observed during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Atterberg Limits
- Percent finer than No. 200 sieve

The laboratory testing program included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.

Site Location and Exploration Plans

Contents:

Site Location Plan

Exploration Plan

Note: All attachments are one page unless noted above.

Geotechnical Engineering Report

Express Oil Change – Stillwater, OK | Stillwater, Oklahoma

October 18, 2024 | Terracon Project No. 04245192



Site Location




Geotechnical Engineering Report

Express Oil Change – Stillwater, OK | Stillwater, Oklahoma

October 18, 2024 | Terracon Project No. 04245192



Exploration Plan



Exploration and Laboratory Results

Contents:

Boring Logs (B-1 through B-7) (7 pages)

Note: All attachments are one page unless noted above.





Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1166° Longitude: -97.1182° Depth (Ft.) Elevation: 102 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
											LL-PL-PI	
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown										
				X	10	7-9-9 N=18		9.2				
				X	11	14-17-13 N=30		8.4				
2		3.5 98.5 SANDY SILTY LEAN CLAY (CL-ML) , brown and reddish brown, soft to medium stiff	5		X	11	3-3-3 N=6		13.7			55
				X	12	2-2-1 N=3		20.8		24-18-6		
				X	10	2-2-2 N=4		22.2				
				▽								
				▽								
				X	13	0-0-2 N=2		21.6				
				X	14	3-4-5 N=9		23.3				
		20.0 82 Boring Terminated at 20 Feet	20									

Boring Started
10-03-2024

Boring Completed
10-03-2024

[illegible]Facilities | Environmental | **Geotechnical** | Materials

Boring Log No. B-3

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1169° Longitude: -97.1182° Depth (Ft.) Elevation: 101.5 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
											LL-PL-PI	
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown 3.5 98				10	7-7-9 N=16		7.8			
							17-8-5 N=13		7.1			
2		SANDY LEAN CLAY (CL) , with silt lenses, brown and reddish brown, soft to medium stiff 10.0 91.5	5			10	7-4-2 N=6		9.7		25-17-8	
							2-2-2 N=4		16.0			
							1-2-3 N=5		22.6			
		Boring Terminated at 10 Feet	10									

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Water Level Observations
 Not encountered while drilling
 Not encountered after drilling

Drill Rig
 CME550/ATV
Hammer Type
 Automatic
Driller
 TS



Notes

Advancement Method
 Hollowed Stem Auger

Logged by
 DS
Boring Started
 10-03-2024
Boring Completed
 10-03-2024



Abandonment Method
 Boring backfilled with auger cuttings upon completion.

Boring Log No. B-4

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1168° Longitude: -97.1184° Depth (Ft.) Elevation: 101.5 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
											LL-PL-PI	
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown	2.0			10	9-5-8 N=13		7.2			
2		SANDY SILTY LEAN CLAY (CL-ML) , brown and reddish brown, soft to medium stiff	99.5			12	3-3-2 N=5		9.8			53
						13	2-2-2 N=4		15.7			
						10	2-2-3 N=5		18.2			
						10	2-2-2 N=4		21.5			
		Boring Terminated at 10 Feet	10.0									

Notes	See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations.	Water Level Observations Not encountered while drilling Not encountered after drilling	Drill Rig CME550/ATV Hammer Type Automatic Driller TS
		Advancement Method Hollowed Stem Auger Abandonment Method Boring backfilled with auger cuttings upon completion.	Logged by DS Boring Started 10-03-2024 Boring Completed 10-03-2024

Boring Log No. B-5

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1168° Longitude: -97.1181° Depth (Ft.) Elevation: 102 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown	3.5				17-4-7 N=11		6.9			
							15-14-9 N=23		11.6			
2		SANDY SILTY LEAN CLAY (CL-ML) , brown and reddish brown, soft to medium stiff	98.5				3-3-3 N=6		12.9		25-19-6	
							3-2-3 N=5		17.3			
							1-1-1 N=2		20.1			
		Boring Terminated at 10 Feet	10.0									

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Water Level Observations
 Not encountered while drilling
 Not encountered after drilling

Drill Rig
 CME550/ATV
Hammer Type
 Automatic
Driller
 TS






Notes

Advancement Method
 Hollowed Stem Auger

Logged by
 DS
Boring Started
 10-03-2024
Boring Completed
 10-03-2024

Abandonment Method
 Boring backfilled with auger cuttings upon completion.

Boring Log No. B-6

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1165° Longitude: -97.1184° Depth (Ft.) Elevation: 102 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
											LL-PL-PI	
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown	3.5			8	8-8-7 N=15		8.5			
						10	10-6-6 N=12		9.3			
2		SILTY SAND (SM) , brown and reddish brown, loose	5			11	3-4-4 N=8		11.4			48
						12	3-3-3 N=6		16.9			
						10	1-3-3 N=6		20.5			
		Boring Terminated at 10 Feet	10									

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Water Level Observations
 Not encountered while drilling
 Not encountered after drilling

Drill Rig
 CME550/ATV
Hammer Type
 Automatic
Driller
 TS








Notes

Advancement Method
 Hollowed Stem Auger

Logged by
 DS
Boring Started
 10-03-2024
Boring Completed
 10-03-2024

Abandonment Method
 Boring backfilled with auger cuttings upon completion.

Boring Log No. B-7

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 36.1165° Longitude: -97.1181° Depth (Ft.) <div>Elevation: 101 (Ft.) +/-</div>	Depth (Ft.)	Water Level Observations	Sample Type	Recovery (In.)	Field Test Results	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1		6" Topsoil FILL - CLAYEY SAND , with sandstone fragments, trace gravel, brown and dark brown 3.5 97.5	5			10	17-27-19 N=46		8.0			
					11	4-3-3 N=6	6.6					
					13	2-2-2 N=4	14.1					
					18	2-2-3 N=5	20.6					
2		SANDY LEAN CLAY (CL) , with silt lenses, brown and reddish brown, soft to medium stiff 10.0 91	10			10	3-3-3 N=6		22.0		27-16-11	
Boring Terminated at 10 Feet												

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Water Level Observations
 Not encountered while drilling
 Not encountered after drilling

Drill Rig
 CME550/ATV
Hammer Type
 Automatic
Driller
 TS

Notes

Advancement Method
 Hollowed Stem Auger

Logged by
 DS
Boring Started
 10-03-2024
Boring Completed
 10-03-2024

Abandonment Method
 Boring backfilled with auger cuttings upon completion.

Supporting Information






Contents:

General Notes

Unified Soil Classification System

Note: All attachments are one page unless noted above.

General Notes

Sampling	Water Level	Field Tests
 Split Spoon	 Water Initially Encountered  Water Level After a Specified Period of Time  Water Level After a Specified Period of Time  Cave In Encountered Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations.	N Standard Penetration Test Resistance (Blows/Ft.) (HP) Hand Penetrometer (T) Torvane (DCP) Dynamic Cone Penetrometer UC Unconfined Compressive Strength (PID) Photo-Ionization Detector (OVA) Organic Vapor Analyzer

Descriptive Soil Classification

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

Location And Elevation Notes

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

Strength Terms

Relative Density of Coarse-Grained Soils (More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance		Consistency of Fine-Grained Soils (50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance		
Relative Density	Standard Penetration or N-Value (Blows/Ft.)	Consistency	Unconfined Compressive Strength Qu (tsf)	Standard Penetration or N-Value (Blows/Ft.)
Very Loose	0 - 3	Very Soft	less than 0.25	0 - 1
Loose	4 - 9	Soft	0.25 to 0.50	2 - 4
Medium Dense	10 - 29	Medium Stiff	0.50 to 1.00	4 - 8
Dense	30 - 50	Stiff	1.00 to 2.00	8 - 15
Very Dense	> 50	Very Stiff	2.00 to 4.00	15 - 30
		Hard	> 4.00	> 30

Relevance of Exploration and Laboratory Test Results

Exploration/field results and/or laboratory test data contained within this document are intended for application to the project as described in this document. Use of such exploration/field results and/or laboratory test data should not be used independently of this document.

Unified Soil Classification System

Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests ^A				Soil Classification	
				Group Symbol	Group Name ^B
Coarse-Grained Soils: More than 50% retained on No. 200 sieve	Gravels: More than 50% of coarse fraction retained on No. 4 sieve	Clean Gravels: Less than 5% fines ^C	$Cu \geq 4$ and $1 \leq Cc \leq 3$ ^E	GW	Well-graded gravel ^F
			$Cu < 4$ and/or $[Cc < 1 \text{ or } Cc > 3.0]$ ^E	GP	Poorly graded gravel ^F
		Gravels with Fines: More than 12% fines ^C	Fines classify as ML or MH	GM	Silty gravel ^{F, G, H}
	Sands: 50% or more of coarse fraction passes No. 4 sieve		Fines classify as CL or CH	GC	Clayey gravel ^{F, G, H}
		Clean Sands: Less than 5% fines ^D	$Cu \geq 6$ and $1 \leq Cc \leq 3$ ^E	SW	Well-graded sand ^I
			$Cu < 6$ and/or $[Cc < 1 \text{ or } Cc > 3.0]$ ^E	SP	Poorly graded sand ^I
Fine-Grained Soils: 50% or more passes the No. 200 sieve	Silts and Clays: Liquid limit less than 50		Fines classify as ML or MH	SM	Silty sand ^{G, H, I}
			Fines classify as CL or CH	SC	Clayey sand ^{G, H, I}
		Inorganic:	$PI > 7$ and plots above "A" line ^J	CL	Lean clay ^{K, L, M}
	Silts and Clays: Liquid limit 50 or more		$PI < 4$ or plots below "A" line ^J	ML	Silt ^{K, L, M}
		Organic:	$\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$	OL	Organic clay ^{K, L, M, N}
					Organic silt ^{K, L, M, O}
Highly organic soils:		Inorganic:	PI plots on or above "A" line	CH	Fat clay ^{K, L, M}
			PI plots below "A" line	MH	Elastic silt ^{K, L, M}
		Organic:	$\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$	OH	Organic clay ^{K, L, M, P}
	Primarily organic matter, dark in color, and organic odor				Organic silt ^{K, L, M, Q}
				PT	Peat

^A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

^C Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.

^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

^E $Cu = D_{60}/D_{10}$ $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$

^F If soil contains $\geq 15\%$ sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

^H If fines are organic, add "with organic fines" to group name.

^I If soil contains $\geq 15\%$ gravel, add "with gravel" to group name.

^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.

^K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.

^L If soil contains $\geq 30\%$ plus No. 200 predominantly sand, add "sandy" to group name.

^M If soil contains $\geq 30\%$ plus No. 200, predominantly gravel, add "gravelly" to group name.

^N $PI \geq 4$ and plots on or above "A" line.

^O $PI < 4$ or plots below "A" line.

^P PI plots on or above "A" line.

^Q PI plots below "A" line.

